Work Specifications and Market Rates

Jobs Without Lots :

Job: Restructring and Renovation of C3A Offices at NUST H-12, Islamabad

Specifications / Requirements:

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
1	Note	The Estimate is based on MES Schedule of Rates, 2025 and market.				
2	A.	CIVIL Works				

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
3	7-198.	Taking down partitions, framing, cupboard front, wall panelling and similar woodwork, including doors exceeding 2.60 m each Hard / Soft wood and re-fixing in other opening.	Sqm	50	1523	76150

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
4	7-66.	Supply Aluminium Swing door, Single shutter, Deluxe Quality of Anodized Aluminium extruded section in any size, colour and texture as specified including fixing on concrete, wooden or steel frames, complete Except glass, lock and handle.	Sqm	9.66	18486	178574.76
5	28-6.	Aluminium Door Handle, Deluxe Quality.	Each	4	3500	14000

PUBLIC PROCUREMENT REGULATORY AUTHORITY PPRA EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
6	8-7.	Supply and fix 150 mm long, CP tower bolts with bright shoots, and fixed with sockets or let into any material.	Each	20	348	6960
7	8-206.	Supply and fix, Aluminium door closer, Deluxe Model, Anodized Bronze.	Each	15	3663	54945
8	8-204.	Supply and fix, Aluminium door lock, Delux model, Anodized Bronze.	Each	10	2266	22660

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
9	7-68.	Fixing only, Aluminium door any type on concrete, wooden or steel frames, complete, except glass, lock and handle.	Sqm	31.36	703	22046.08
10	15-4 + 15-5.	Distempering with Poly Vinyl Distemper or equivalent, on new or old surface, 1st Coat, 2nd and Subsequent Coat.	Sqm	1720	203	349160

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
11	15-101.	Surface preparation by using putty on plastered wall or ceiling to form smooth base for distemper, plastic emulsion paint etc., all as specified.	Sqm	300	176	52800
12	15-18 + 15-19.	1st, 2nd & Subsequent Coat of painting to new or old work such as doors of any type and description with synthetic enamel paint.	Sqm	100	475	47500

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
13	13-4.	Cement Plaster 1:4, 13 mm thick finished as specified (Basement, GF, FF and 2nd floor).	Sqm	80	795	63600
14	12-67.	Providing and laying artificial wooden / laminated tiles, 8 mm thick, all as specified.	Sqm	320	3258	1042560
15	12-33.	Cleaning and chemical polishing of terrazzo floor / dado / Marble floors.	Sqm	219.4	333	73060.2

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
16	16-14.	Supply and fix, Tinted Sheet glass 5 mm thick, fixed to timber or steel sashes with putty as specified.	Sqm	16	5173	82768
17	7-136.	Supply and fix,12mm thick Plate Glass partition/door in any size including all necessary accessories i.e. pivot machine, handle lock etc.	Sqm	27.32	15000	409800
18	16-21.	Tempering to any thickness of glass sheet, all as specified.	Sqm	185	4813	890405

PUBLIC PROCUREMENT REGULATORY AUTHORITY PPRA EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
19	16-19.	Supply and fix Frosted paper of any design/ pattern over plain glass complete, all as specified.	Sqm	185	1900	351500
20	12-35.	Providing and laying Standard quality tiles of any make not exceeding 1600 Sq cm, including setting, jointing and bonding, complete all as specified.	Sqm	50	3868	193400

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
21	MR BTS	Supply & Fix 12mm tempered glass including aluminium section/channel fix as required as per drawing & specs complete in all respects	Sqm	157.68	10878.36	1715299.8048
22	MR BTS	Tile grouting/filling in joint including racking out old joints, filling and cleaning of floors	Sqm	72	282.45	20336.4

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
23	MR BTS	Supply & Fix Dry partition Cement board 12 mm thickness with G,I Steel Stud and track framework Double Side securely fixed to structural elements, jointing tape, joint filling including door(with accessories) and accessories complete in all respects.	Sqm	92.5	15473	1431252.5

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
24	MR BTS	Providing & Sealing of gaps around sheds & windows (incl. gaskit, silicon etc) by removing all lose, weak, defective material, cleaning joint thoroughly and apply manufecturer recmonded primer and filling joints with approved single component elastomeric polyurethene sealent (sikaflex or approved equilent). sealent to be applied using appropriate	Sqm	45	2304.79	103715.55

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
25	B.	ELECTRICAL Works				
26	24-12	One fan point or one light point or one bell point, controlled by one switch, wiring complete, with PVC single core cable 1.5 mm², in Surface conduit, stove enamelled, supply and fixing.	point	15	3072	46080

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
27	24-194	LED strips light 4 feet, 36 watt 220/240 volts for wall or ceiling mounted approved type Deluxe Supply and fixing. (4000K)	Each	40	2144	85760
28	24-206	LED Recessed panel light 18 watts, 220/240 volts, round or Square, approved type, deluxe Supply and fixing.	Each	15	2341	35115

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
29	24-149	One three pin socket outlet, 15 A, point controlled by one switch, wiring complete with PVC single core cable 2.5 mm2, on PVC Channel Patty, including earth wire, supply and fixing.	Point	25	3088	77200
30	24-474	Wall Bracket Fan Fancy with copper winding, plastic body 12” & 14” “Deluxe” Supply & fixing.	Each	2	7379	14758

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
31	24-461	Clamp hook for fan, ordinary type, supply and fixing.	Each	15	491	7365
32	24-466	Fan electric with copper winding, blades, canopy and rod including connection, provision of cable and ceiling rose, for fan 140 cm and 120 cm sweep, without regulator “Deluxe”, supply and fixing.	Each	6	11363	68178

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
33	24-792	Multi socket Light Plug, 10A, 250 V including PVC / steel back box with proper screws Complete, supply and fixing.	Each	30	1141	34230
34	24-793	Gang Power Socket, 15A, 250 V including PVC/steel back box with proper screws complete, supply & fixing.	Each	10	1116	11160
35	24-804	Same as item 24-801, but Four gang switch.	Each	6	1082	6492

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
36	24-827	Same as item 24-815, 5 Step Fan speed controller including PVC / steel back box with proper screws.	Each	6	1653	9918

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
37	24-611	Wiring in conduit surface, concealed, flame proof, with single core PVC insulated cable, installed and connected complete (excluding conduit) single core cable, 2.5 mm², supply and fixing.	meter	180	136	24480

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
38	24-612	Wiring in conduit surface, concealed, flame proof, with single core PVC insulated cable, installed and connected complete (excluding conduit) single core cable, 4 mm^2, supply and fixing.	meter	180	179	32220
39	24-366	MCCB, SP, 6 to 63 A. (Breaking capacity 6 KA), supply and fixing	Each	8	1104	8832

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
40	BTS	Supply and Fixing of PVC Dust 16x38 adam jee or approved equvilent complete in all respect.	Meter	70	200	14000
41	C.	HVAC Works				

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
42	MR	Supply and installation of wall mounted split AC inverter type 1.5 Ton (18000 BTU/Hr) capacity with remote, filter, and outdoor red oxide stand, T3 compressor technology and 75% efficient energy model, including core cutting and 10’ copper kit (Brand: Hisense/ Orient)	No.	3	200000	600000

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
43	MR	Shifting of old ACs to new locations with complete work including removal and re-installation of Ac indoor / outdoor unit, copper piping, drain piping, control wiring, core cutting and outdoor shifting	No.	12	5625	67500

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
44	MR	Supply and installation of extra copper piping (22g) with insulation, fittings and control wiring, proper wrapping complete in all respect (Brand: Royal/ Mueller/ GD)	Rft	250	1562.5	390625
45	MR	Supply and installation of extra drain piping UPVC 3/4 inch with complete fitting and pipe solution (Brand: popular/beta)	Rft	250	168.75	42187.5

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS

Sr. No	Ref No.	Description	Unit	Quantity	Rate	Amount
46	MR	Supply and installation dura duct 60mm x 60mm with complete fittings and accessories, for covering of copper piping, drain piping and control wiring (Adamjee/ beta)	Rft	250	275	68750
					GRAND TOTAL:	Rs8,847,343.79

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS