Work Specifications and Market Rates

Jobs Without Lots :

Job: BOQ - Civil Works

Specifications / Requirements:

Sr. No	S. No	Description	Unit	Quantity	Rate	Amount
1	1	Providing, supplying and fixing of raised access flooring system comprising calcium sulphate core tiles 600×600 mm, 38–40 mm thick, with HPL anti-static laminated top surface of matching colour and galvanized/metal sheet backing, complete with adjustable stainless steel pedestals, stringers and rigid supporting frame, to achieve finished floor level (FFL) height 300–450 mm, of MERO (Germany) / Marflex or approved equivalent, including all necessary accessories such as edge trims, ramps, cut-outs for services, fasteners, levelling, alignment, during installation and cartage to site, supply and installation complete in all respects as per manufacturer’s specifications and directions of the Engineer-in-Charge.	P.Sft	432 Sft		-

Sr. No	S. No	Description	Unit	Quantity	Rate	Amount
2	2	Providing and fixing Plaster of Paris tiles size (2' x 2' x 3/4") for false ceiling i/c Aluminum T and L angle 1" x 1" i.c hanger clips jointing clips and g.I. Wire etc complete as required in any floor.	P.Sft	280 Sft		-
3	3	Providing and fixing fully glazed Bronze anodized or Powder Coated aluminum Fixed windows Partition as per British standard manufactured by Lucky, Alcop, Krudson, Pakistan Cables and A.C.P. (fixing through approved fabricators) Deluxe model box section 101.76mm x 44.50mm and 1.6mm thick including the cost of aluminum fittings, with all accessories cutting hole etc. and making good damages to walls etc. complete as required in any floor as per direction of engineer-in-charge, but excluding the cost of glass pans.	P.Sft	499 Sft		-
4	4	Providing and fixing double glazed Bronze anodized or Powder Coated aluminum Sliding windows as per British standard manufactured by Lucky, Alcop, Krudson, Pakistan Cables and A.C.P. (fixing through their approved fabricators), Executive model section double or single glazed 101mm x 37mm and 1.6mm thick including the cost of aluminum netting ,fitting, with all accessories cutting hole etc. and making good damages to walls etc. making Locking arrangement complete as required in any floor as per direction of engineer-in-charge, but excluding the cost of glass pans.	P.Sft	96 Sft		-

Sr. No	S. No	Description	Unit	Quantity	Rate	Amount
5	5	Providing and fixing plain glass panes 5mm thick to M.S. Box pipe / Aluminum doors, windows and ventilators etc. including the cost of labor but excluding the cost of M.S. square pipe beading, rubber packing and screw in any floor at any height.	P.Sft	595 Sft		-
6	Total					3736150
					GRAND TOTAL:	Rs3,736,150.00

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA) EPADS